

NHF SCHEDULE OF RATES – FOREMASTER – PLANNED MAINTENANCE

These are Planned Maintenance (Foremaster) sample descriptions © Rand Associates Ltd from www.m3h.co.uk

Provides all the documentation for *planning, specifying and estimating the costs* of major works programmes. It is used for stock re-investment, planned maintenance and improvements, MRA works and Decent Homes works.

ITEM	LEV	DESCRIPTION	UNIT	RATE
6309AA	30	<p>Baths - Nominated Supplier BATH:RENEW 1700MM STEEL Bath:Renew upto 1700mm heavy duty vitreous enamel steel bath complete with new taps and waste fitting, reconnect existing supply pipework including any adjustments, provide new service valves if not already installed, complete with new plug and chain, plastic trap, connect to waste pipework, 4.8mm self finished hardboard bath panels screwed with chromium plated dome headed screws to and including 38x50mm softwood framing, angle trim, make good existing or renew 300mm high glazed wall tile splashback fixed with adhesive including all labours, silicone sealant between splashback and bath, and crossbond, and remove waste and debris. [Bath PC Sum of £150.00 supplied and delivered complete with taps bath panels and waste fitting ready for installation]</p>	NO	411.14
6309BA	20	<p>BATH:RENEW 1700MM ACRYLIC Bath:Renew 8mm thick Acrylic bath upto 1700mm long complete with new taps and waste fitting, reconnect existing supply pipework including any adjustments, provide new service valves if not already installed, complete with new plug and chain, plastic trap, connect to waste pipework, supply and fix new acrylic bath panels to match including proprietary fixings, make good existing or renew 300mm high glazed wall tile splashback fixed with adhesive including all labours, silicone sealant between splashback and bath, and crossbond, and remove waste and debris. [Bath PC Sum of £150.00 supplied and delivered complete with taps bath panels and waste fitting ready for installation]</p>	NO	397.72
6309CA	30	<p>BATH:INSTALL SPECIAL NEEDS TYPE Bath:Renew bath with special needs bath with rim and internal bath seat complete with new taps and waste reconnect to existing supply pipework including any adjustments, provide new service valves if not already installed, complete with new plug and chain, plastic trap, connect to waste pipework, remove existing bath panels and frame- work and fix new proprietary front and end bath panels including all necessary fixings and supports, make good existing and renew glazed wall tile splashback fixed with adhesive including all rounded edges and labours, silicone sealant between splashback and bath, and crossbond, make good wall and floor finishes, and remove waste and debris. [Bath PC Sum of £410.00 supplied and delivered complete with taps and waste fitting ready for installation]</p>	NO	697.14